



- GENERAL NOTES**
1. Do Not Scale
 2. The contractor is to check and verify all buildings and site dimensions and levels, including sewer invert levels, before works start on site. The contractor is to comply in all aspects with the current building legislation, British Standards, building regulations etc.
 3. Positions of existing services/statutory undertakers apparatus adjacent to or crossing proposed excavations are to be checked by the contractor prior to starting work

Legend

Phoenix 2 Duo Recycler (P2-12W with Elite 6x4 chassis)

Overall Length	10.320m
Overall Width	2.530m
Overall Body Height	3.766m
Min Body Ground Clearance	0.308m
Track Width	2.530m
Lock to lock time	4.00s
Kerb to Kerb Turning Radius	9.450m

B	24/11/20	Site layout revised	PBO	TL	
A	07/08/20	Layout amended	PBO	TL	
-	09/07/20	First Issue	PBO	TL	
REV.	DATE	DETAILS	AMENDMENTS	BY	CHK.

CLIENT:

CONSULTING ENGINEERS
 PHG CONSULTING LTD
 62A ALBANY ROAD
 CARDIFF CF24 3RR
 T: +44(0)29 2030 2521
 E: enquiry@phg-consulting.com
 W: www.phg-consulting.co.uk
 @PHG_consulting
 www.linkedin.com/company/phg-consulting-engineers

PROJECT:
Barratt Homes
 Ty Fry Farm,
 Glebe Road, Loughor

DRAWING TITLE:
Tracking Layout
Refuse Vehicle
 Sheet 1 of 5

DRAWN	CHK	STATUS	SCALE
PBO	TL	Planning	1:250 @ A1
DATE	JOB NO.	DWG. NO.	REV.
Jul-20	2071	002-1	B